



8-Core Outdoor Fiber Termination Box (ODF) — plastic — empty (no pigtails)

بۆكسى تېرمىنالى فايهر دهره وه 8 كۆر (ODF) — پلاستىك — به تال
صندوق إنهاء ألياف خارجي 8 كور (ODF) — بلاستيك — فارغ

ISH-P158

ISHCO

OVERVIEW

Weatherproof 8-core outdoor termination box for FTTH drops — IP65
ABS/PC housing with splice tray, wall or pole mounting. Supplied empty so
you fit your own pigtails and adapters.

بۆكسى تېرمىنالى دهره وه 8 كۆر بۆ FTTH — كه يسى ABS/PC ي IP65 به ته باقى
سپلايس، بۆ ديوار يان كۆله كه. به تال ده نيردرېت تا پيگته يل و نه دا پته رى خوت دا بئيت.

صندوق إنهاء خارجي 8 كور مقاوم للطقس لتوزيع FTTH — هيكل ABS/PC بحماية IP65
مع صينية لحام، تركيب حائطي أو على عمود. يُوزد فارغًا لتركيب البيغتل والمحولات الخاصة
بك.

ISHCO
photo on request

KEY FEATURES

- IP65 weatherproof, UV-stabilised housing
- 8 cores, SC adapter ports
- Splice tray included
- Wall or pole mounting
- Supplied empty — fit your own pigtails

SPECIFICATIONS

Capacity	8 cores · 8 × SC simplex adapter ports (not fitted)
Type	Outdoor FTTH fibre termination / distribution box
Material	ABS + PC, UV-stabilised
Protection	IP65 weatherproof, lockable
Mounting	Wall or pole mount (brackets included)
Includes	1 splice tray, cable entry glands, fixing kit — supplied empty (no pigtails / adapters)
Cable	2 inlet ports (feeder cable up to 10 mm) + drop cable outlets
Operating temperature	−40 °C to +60 °C